EXTERIOR FINISH SCHEDULE

INSTALLED AND FURNISHED BY..G.C. UNLESS NOTED OTHERWISE

NO	MANUFACTURER	MFG#	COLOR	FINISH	NOTES
EIFS-1	STO	STOTHERM ESSENCE SYSTEM	SW 6148 WOOL SKEIN	FINE	BUILDING BODY
EIFS-2	STO	STOTHERM ESSENCE SYSTEM	SW 7067 CITY SCAPE	FINE	BUILDING BODY
ECT-1	PANTHEON CRYSTAL BANKS: 972-360-9752	EDGE (8 x 60) (TAVERN SERIES)	760-701		BUILDING ACCENT TILE *
ST-1S	CORONADO	CHISELED STONE SILL	LIGHT GREY		STONE CAP
ST-1	CORONADO	INDUSTRIAL EDGE	SHADE GREY		ENTRY PORTAL & WAINSCOT
TR200	SCHLUTER	RONDEC - RO60	AGR		OUTSIDE CORNER TRIM FOR EXTERIOR TILE

* NOTE: INSTALL ECT-1 WITH GROUT - MFG. MODEL # T.B.D. BY T.B.D., COLOR T.B.D. GROUT JOINT SIZE: 1/8" GC TO VERIFY SUITABILITY OF GROUT WITH CERAMIC TILE APPLICATION AND NOTIFY PANDA PM OF ANY ISSUES.

TILE SCHEDULE

INSTALLED AND FURNISHED BY..G.C. UNLESS NOTED OTHERWISE

10-23-15

NO.	MANUFACTURER	DESCRIPTION	COLOR	FINISH	JOINT	GROUT	REMARK
T-96	NOT USED						
T-96a	NOT USED						
T-105	NOT USED						
T-108	CMC AGGREGATE DOUG SALATINO 518-713-5371	12" X 24" X 3/8"	-	-	1 / 8"	G-111	RESTROOM WALL
T-109	CMC ITALIAN WOOD DOUG SALATINO 518-713-5371	6" X 48 X 3/8" & 8" X 48" X 3/8"	ITALIANO	-	1 / 8"	G-113	RR VESTIBULE & DINING ROOM WALLS AND FACE OF ORDER COUNTER
T-110	NOT USED						
T-200	PANTHEON CRYSTAL BANKS: 972.360.9752	24" X 24"	150-4004	MATTE	1/8"	G-96	DINING & RESTROOM FLOOR AND BASE AT ORDER COUNTER
QT	CMC OBIDOS SMOOTH QUARRY 800.207.2967 EXT. 7263	8" X 8" QUARRY	RICE GRAIN	PLAIN	3 / 16"	G-94	KITCHEN, SERVICE FLOOR
QT1	CMC OBIDOS ABRASIVE QUARRY 800.207.2967 EXT. 7263	8" X 8" QUARRY	RICE GRAIN	ABRASIVE	3 / 16"	G-94	KITCHEN, SERVICE FLOOR
QT2	CMC OBIDOS COVE BASE 800.207.2967 EXT. 7263	6" X 12" COVE BASE 1" X 6" CORNER	RICE GRAIN	PLAIN	3 / 16"	G-94	KITCHEN, SERVICE FLOOR

GROUT	MANUFACTURER	DESCRIPTION	MFG.	COLOR	FINISH	REMARK
G-94	MAPEI 800.42.MAPEI WWW.MAPEI.COM	LATEX MODIFIED GROUT	09	GREY	SANDED	KITCHEN AND SERVICE AREA FLOOR. 100% SOLIDS INDUSTRIAL GRADE EPOXY GROUT SEE PLAN. CONTACT: MIKE GRANATOWSKI 949.212.2363 (mgranatowski@mapi.com)
G-96	PANTHEON COMPLETE INSTALLATION SYSTEM	ULTRAFLEX LFT MORTAR ULTRACOLORPLUS GROUT, SPACERS, TROWELS	11	SAHARA BEIGE	POLY BLEND 1 / 8" NON-SANDED	DINING & RESTROOM FLOOR CONTACT: CRYSTAL BANKS 972.360.9752
G-111	MAPEI 800.42.MAPEI WWW.MAPEI.COM	LATEX MODIFIED GROUT	19	PEARL GREY	POLY BLEND 1 / 8" NON-SANDED	RESTROOM , DINING APPLY GROUT SEALER
G-113	MAPEI 800.42.MAPEI WWW.MAPEI.COM	LATEX MODIFIED GROUT	07	CHOCOLATE	POLY BLEND 1 / 8" NON-SANDED	APPLY GROUT SEALER

REFER A-200 EXTERIOR FINISH SCHEDULE FOR EXTERIOR DECORATIVE TILE

SCHLUTER SYSTEM ALUMINUM TRIM:

COVE TILE TRIM: INSTALLED AT RESTROOM, SERVICE COUNTER, AND DRINK STATION

SCHLUTER SYSTEMS DILEX-AHK 1S 125 ATGB (BRUSHED NICKEL ANODIZED ALUMINUM)

TR100
- -OUTSIDE CORNER CONNECTOR PIECE: DILEX-AHK-E90/AHK 1S 125 ATGB (BRUSHED NICKEL ANODIZED ALUMINUM)
- -INSIDE CORNER CONNECTOR PIECE: DILEX-AHK-I90/AHK 1S 125 ATGB (BRUSHED NICKEL ANODIZED ALUMINUM)
- -END CAP PIECE: DILEX-AHK-E/AHK 1S 125 ATGB (BRUSHED NICKEL ANODIZED ALUMINUM)

EDGE TILE TRIM:

SCHLUTER SYSTEMS RONDEC-RO125 ATGB (BRUSHED NICKEL ANODIZED ALUMINUM)

TR101
- -OUTSIDE CORNER CONNECTOR PIECE: RONDEC-EV/RO125 ATGB (BRUSHED NICKEL ANODIZED ALUMINUM)
- -INSIDE CORNER CONNECTOR PIECE: RONDEC-I2L/RO125 ATGB (BRUSHED NICKEL ANODIZED ALUMINUM)

EPOXY GROUT BY MAPEI, KERAPOXY IEG, 100% SOLIDS INDUSTRIAL GRADE:
AREAS: UNDER HOOD AND 36 " IN FRONT OF COOKING LINE, 3 COMPARTMENT SINK AND MOP SINK AREA

SEE MANUFACTURER'S SPECIFICATION, DETAILS AND GUIDE FOR PREPARATION, MIXING, GROUTING AND CLEANING INSTRUCTION

NOTE: SEE INTERIOR SHEETS FOR WALL/ BASE TILE LOCATIONS AND SPECIFICATIONS

TOILET ACCESSORY SCHEDULE

NO	DESCRIPTION
RG36	BOBRICK GRAB BAR, 36" LONG B-6806 1 1/2" , SATIN FINISH
RG42	BOBRICK GRAB BAR, 42" LONG B-6806 1 1/2" SATIN FINISH
RG18	BOBRICK GRAB BAR, 18" LONG B-6806 1 1/2" SATIN FINISH
RM	BOBRICK CHANNEL FRAME MIRROR B-165 (1836) 18"X36" STAINLESS STEEL CHANNEL FRAME
RS	SOAP DISPENSER (BY VENDOR)
RMS	BOBRICK SEAT COVER DISPENSER B-221 STAINLESS STEEL, SATIN FINISH
RTR	BOBRICK SURFACE MOUNTED TRASH RECEPTACLE MODEL # B-275, PROVIDED AND INSTALLED BY G.C.
RHD	PAPER TOWEL DISPENSER FURNISHED BY PANDA AND INSTALLED BY G.C.
RMT	BOBRICK MUTI-ROLL TOILET TISSUE DISPENSER B-2888 STAINLESS STEEL, SATIN FINISH
RT	AMERICAN STANDARD CADET RIGHT HEIGHT ELONGATED TOILET 2467.016 TLT, 4142.600 TANK, AMERICAN STANDARD #5321.110 SEAT, COLOR: WHITE. TRIP TO BE ON OPEN SIDE.
RL	KOHLER UNDER MOUNTED LAVATORY K-2214-G-0, 18" X 12" VITREOUS CHINA, WITH 4" CENTER FAUCET HOLES PROVIDED AND INSTALLED BY G.C.
RD	BOBRICK SURFACE-MOUNTED SANITARY NAPKIN DISPOSAL B-254 STAINLESS STEEL, SATIN FINISH
RH	BOBRICK SURFACE-MOUNTED CLOTHES HOOK AND BUMPER B-212 SOLID ALUMINUM CASTING, MATTE FINISH, INSIDE OF RESTROOM DOORS

* INSULATE TRAP & HOT WATER AT HANDICAPPED LAVS.

LIGHTING FIXTURE SCHEDULE

PROVIDED FOR INFORMATION ONLY.
VERIFY AND INSTALL PER ELECTRICAL DRAWING

02-13-17

ITEM	SYMBOL	DESCRIPTION	QTY.	MFR. □ CAT. NO.	REMARK
INTERIOR LIGHTING ITEM					
L1	L1	RECESSED MOUNTED FLAT PANEL LED 2' X 4' TROFFER, 3500K	REFER TO ELECTRICAL SHEET E-001 FOR LIGHTING FIXTURE QUANTITY	LSI FIXTURE: ELFP24-LED-35-UE	FURNISHED BY OWNER INSTALLED BY GC
L1EM	L1EM	RECESSED MOUNTED FLAT PANEL LED 2' X 4' TROFFER, 3500K, EMERGENCY BATTERY		LSI FIXTURE: ELFP24-LED-35-UE-EM	FURNISHED BY OWNER INSTALLED BY GC
L2	L2	RECESSED MOUNTED FLAT PANEL LED 2' X 2' TROFFER, 3500K, EMERGENCY BATTERY		LSI FIXTURE: ELFP22-LED-35-UE-EM	FURNISHED BY OWNER INSTALLED BY GC
L4	L4	UNIVERSAL MOUNT LED EXIT SIGN WITH BATTERY PACK, 2 FACE, GREEN LETTER		EXITRONIX FIXTURE: GVEX-U-BP-WB-BL-R6	FURNISHED BY OWNER, INSTALLED BY GC
L6A	L6A	HOOD LIGHT		FURNISHED & INSTALLED BY EQUIPMENT SUPPLIER	LIGHTS SUPPLIED & PRE-WIRED BY HOOD VENDOR. ELEC. CONTRACTOR TO CONNECT MAIN WIRES TO SHUNT TRIP BREAKER AND HOOD CONTROL PANEL
L6B	L6B	WALK-IN COOLER FLUORESCENT LIGHT, 48"		KASON FIXTURE: 18180F00048	FURNISHED BY WIC VENDOR, G.R.E., INSTALLED BY GC
L19	L19	DOWN LIGHT, RECESSED IN CEILING		ELITE HOUSING: LD6IC-AT LED MODULE: RL607-750L-DIMTR-120-30K-FL-SN-SN	FURNISHED BY OWNER, INSTALLED BY GC
L19EM	L19EM	EMERGENCY DOWN LIGHT, RECESSED IN CEILING		ELITE HOUSING: LD6IC-AT LED MODULE: RL607-750L-DIMTR-120-30K-FL-SN-SN	EMERGENCY RECESSED DOWN LIGHT - NORMALLY ON FURNISHED BY OWNER INSTALLED BY GC
L20	L20	3-3/4" APERTURE ADJUSTABLE ELBOW LYTECASTER RECESSED DOWNLIGHT		LIGHTOLIER FRAME-IN KIT: 302MRSPX REFLECTOR TRIM: 378WHX BULB: LED5.5DMR1683035	FURNISHED BY OWNER, INSTALLED BY GC
L26	L26	DECORATIVE PENDANT LIGHT		CASEY ARCHITECTURAL LIGHTING (2) A_ROUND: PE-RND, (2) B_ONION: PE-ONI (2) C_OBLONG: PE-OBL, (2) D_BARREL:PE-BAR BULB: ST-64 CLEAR #41098	FURNISHED BY OWNER, INSTALLED BY GC. REFER TO RCP FOR HEIGHT.
L30	L30	WHITE LED MODULES MOUNTED IN SOFFIT		ZLED LIGHTING FIXTURE: MOD-R-5050-WW	FURNISHED BY OWNER, INSTALLED BY GC
L35	L35	9.8" DIA. DECORATIVE ISLA PENDANT		LBL LIGHTING FIXTURE: LF512CRSC BULB: ST-64 CLEAR #41098	FURNISHED BY OWNER, INSTALLED BY GC. REFER TO RCP FOR HEIGHT.
L100	W100	110 WATT MINI INVERTER RATED FOR 90 MIN.		EELP FIXTURE: PS-110-HP-S	FURNISHED BY OWNER, INSTALLED BY GC
L101	W101	110 WATT MINI INVERTER RATED FOR 90 MIN.		EELP FIXTURE: PS-110-HP-S	FURNISHED BY OWNER, INSTALLED BY GC (VERIFY EXACT INVERTER WITH VILLA LIGHTING)
EXTERIOR LIGHTING					
L85A		LED WALL SCONCE MOUNTED OVER DOOR	REFER TO ELECTRICAL SHEET E-001 FOR LIGHTING FIXTURE QUANTITY	HOWARD LIGHTING FIXTURE: VL20	FURNISHED BY OWNER, INSTALLED BY GC, REFER TO ARCHITECTURAL ELEVATION
L86		REMOTE LED EMERGENCY EGRESS LIGHT		MLED1-G-WP	10'-0" AFF, FURNISHED BY OWNER, INSTALLED BY GC
L86A		RECESSED EMERGENCY LIGHT UNDER RED ENTRANCE PORTAL		ELITE HOUSING: LD6IC-AT LED MODULE: RL607-750L-DIMTR-120-30K-FL-SN-SN	NORMALLY ON, FURNISHED BY OWNER INSTALLED BY GC
L90	L90	DECORATIVE WALL SCONCE		HINKLEY LIGHTING FIXTURE: ATLANTIS 1644BZ-LED BULB: LED5.5DMR1683035	FURNISHED BY OWNER, INSTALLED BY GC

NIGHT LIGHTING REQUIREMENTS: "NL" DESIGNATION INDICATED NIGHT LIGHT ON UNSWITCED CIRCUIT.
1. ONE NL BY SERVICE COUNTER, POS / CASHIER
2. ONE NL BY POS / CASHIER AT DRIVE THRU STATION IF APPLICABLE
3. ONE NL BY EACH EXIT DOORS IN DINNING ROOM □ BACK OF HOUSE
4. ONE NL BY MANAGER STATION

CEILING SCHEDULE

INSTALLED AND FURNISHED BY..G.C. UNLESS NOTED OTHERWISE

NO	MANUFACTURER	DESCRIPTION	MATERIAL	FINISH
C1	ARMSTRONG	2' X 2' SUSPENDED T-BAR GRID CEILING SYSTEM	CUSTOM #PN91311	T-BAR AND GRID COLOR: SEPIA CONTACT AT ARMSTRONG - SHERRY BRUNT 1-800-442-4212
C2	USG	2' X 4' SUSPENDED T-BAR GRID CEILING SYSTEM	"VINYL ROCK" VINYL CLAD GYP. BD PANELS	SMOOTH AND WASHABLE WHITE
C3	GOLD BOND	MONOLITHIC CEILING ON METAL FRAMING	5/8" GYP. BD.	SMOOTH PAINT - WHITE AND WASHABLE

SEE SHEET A-103 FOR PAINT SCHEDULE

WINDOW SCHEDULE

INSTALLED AND FURNISHED BY..G.C. UNLESS NOTED OTHERWISE

SYM	WIDTH	HEIGHT	GLASS	FRAME	REMARKS
A	17'-6"	10'-0"	1" INSULATED GLASS	DARK BRONZE ALUMINUM STOREFRONT	1" INSULATED GLAZING, IN 4.5" X 2" ANODIZED ALUMINUM FRAME
B	19'-3"	10'-0"	1" INSULATED GLASS	DARK BRONZE ALUMINUM STOREFRONT	1" INSULATED GLAZING, IN 4.5" X 2" ANODIZED ALUMINUM FRAME
C	7'-0"	8'-0"	1" INSULATED GLASS	DARK BRONZE ALUMINUM STOREFRONT	1" INSULATED GLAZING, IN 4.5" X 2" ANODIZED ALUMINUM FRAME
D	5'-7"	10'-0"	1" INSULATED GLASS	DARK BRONZE ALUMINUM STOREFRONT	1" INSULATED GLAZING, IN 4.5" X 2" ANODIZED ALUMINUM FRAME
E	7'-3 3/4" (TOTAL)	59 1/2"	TEMPERED GLASS	DARK BRONZE ANODIZED ALUMINUM	QUIK-SERV WITH HEATED AIR CURTAIN. ROUGH OPENING PER 5 / A-201. SEE ADDITIONAL NOTE # 5. CONTACT: STEVE BERT, 800-388-8307

NOTES
1. INSULATING GLASS PPG SOLARBAN 60 LOW E: WINTER U=0.25 SHGC: 0.39 VIS TRANS: 83% UV ENERGY: 46%
2. DOORS: FULL GLAZED DOORS W/10" KICK BASE, COLOR DARK BRONZE ANODIZED ALUM FINISH. REFER HARDWARE SCHEDULE.
3. WINDOW DIMENSIONS ARE FOR BIDDING PURPOSES ONLY. G.C. TO VERIFY ACTUAL WINDOW DIMENSIONS PRIOR TO FABRICATION INSTALLATION.
4. GLASS FACADE AND ENTRY DOORS TO BE DESIGNED, DETAILED, FACTORY FABRICATED AND SITE ASSEMBLED AND ERECTED.
5. MANUFACTURER: QUIK-SERV, MODEL SST-4860E WITH THRU-BEAM WITH PHOTO-ELECTRIC BAR. FURNISH WITH CHF-25 HEATED AIR CURTAIN.
6. WINDOW SYSTEM SHALL COMPLY WITH APPLICABLE SECTION AND CHAPTER 0F BUILDING CODE.

(T) TEMPERED GLASS

FINISH SCHEDULE

ROOM NAME	FLOOR	BASE	WALL	CEILING
100 DINING ROOM	T200 24" X 24" TILE	T109 6" X 48" TILE	P104 PAINT T109 TILE W102 WALL COVERING	C1 2' X 2' ARMSTRONG, SEPIA #PN91311 C3 GYP BOARD W/ PAINT P103
101 SERVING AREA	QT 8" X 8" CONT. QUARRY TILE QT1 IN HIGH TRAFFIC AREAS	QT2 6" X 12" CONT. 3/4" RAD. MIN (KITCHEN EQUIPMENT ON 6" NSF APPROVED LEGS)	T109 TILE	C3 GYP BOARD W/ SMOOTH WASHABLE PAINT
102 DRIVE-THRU STATION	QT 8" X 8" CONT. QUARRY TILE QT1 IN HIGH TRAFFIC AREAS	QT2 6" X 12" CONT. 3/4" RAD. MIN (KITCHEN EQUIPMENT ON 6" NSF APPROVED LEGS)	WP1 FRP PANEL	C2 2' X 4' SUSPENDED GRID WASHABLE VINYL COATED GYP BOARD PANELS
103 KITCHEN	QT 8" X 8" CONT. QUARRY TILE QT1 IN HIGH TRAFFIC AREAS	QT2 6" X 12" CONT. 3/4" RAD. MIN (KITCHEN EQUIPMENT ON 6" NSF APPROVED LEGS)	WP3 S.S. BEHIND COOK LINE WP2 S.S. LEFT END COOKLINE WP1 FRP PANEL	C2 2' X 4' SUSPENDED GRID WASHABLE VINYL COATED GYP BOARD PANELS
104 KITCHEN PREP.	QT 8" X 8" CONT. QUARRY TILE QT1 IN HIGH TRAFFIC AREAS	QT2 6" X 12" CONT. 3/4" RAD. MIN (KITCHEN EQUIPMENT ON 6" NSF APPROVED LEGS)	WP1 FRP PANEL	C2 2' X 4' SUSPENDED GRID WASHABLE VINYL COATED GYP BOARD PANELS
105 WALK-IN COOLER	QT 8" X 8" CONT. QUARRY TILE QT1 IN HIGH TRAFFIC AREAS	S.S. / ALUMINUM WITH 3/4" RADIUS	EXT S.S. INT ALUMINUM GALVANIZED S.S.	ALUMINUM GALVANIZED STAINLESS STEEL
105A WALK-IN FREEZER	GALVANIZED STAINLESS STEEL QT 8" X 8" CONT. QUARRY TILE UNDER WIF SUBFLOOR	S.S. / ALUMINUM WITH 3/4" RADIUS	EXT S.S. INT ALUMINUM GALVANIZED S.S.	ALUMINUM GALVANIZED STAINLESS STEEL
106 MEN'S ROOM	T200 24" X 24" TILE	SCHLUTER	T108 TILE	C3 GYB BOARD W/ P101 SMOOTH WASHABLE PAINT
107 WOMEN'S ROOM	T200 24" X 24" TILE	SCHLUTER	T108 TILE	C3 GYB BOARD W/ P101 SMOOTH WASHABLE PAINT
108 VESTIBULE	T200 24" X 24" TILE	T109 6" X 48" TILE	P104 PAINT GYB BOARD T109 TILE	C3 GYB BOARD W/ P101 SMOOTH WASHABLE PAINT
109 STORAGE ROOM	T200 24" X 24" TILE	T109 6" X 48" TILE	WP1 FRP PANEL	C3 GYB BOARD W/ P101 SMOOTH WASHABLE PAINT
110 NOT USED	-	-		-

DOOR SCHEDULE

INSTALLED AND FURNISHED BY..G.C. UNLESS NOTED OTHERWISE

NO.	DOOR MATERIAL	SIZE	FRAME	FACE/EDGE	THK.	CORE	LITE	RATE	HDW
01	ALUMINUM STOREFRONT	3'-6" X 8'-0"	ALUMINUM	DARK BRONZE ALUMINUM	1 3/4"	HOLLOW	GLASS	-	HW-1 PANIC EXIT REQUIRED
02	ALUMINUM STOREFRONT	3'-0" X 8'-0"	ALUMINUM	DARK BRONZE ALUMINUM	1 3/4"	HOLLOW	GLASS	-	HW-1 PANIC EXIT REQUIRED NO HARDWARE ON EXTERIOR SIDE OF DOOR
03	S.C. WOOD	3'-0" X 7'-0"	H. METAL	L-200, SEE SPECIAL SURFACE SCHEDULE	1 3/4"	SOLID	-	-	HW-4 UNDERCUT DOOR BOTTOM 1" AT RESTROOM
04	S.C. WOOD	2'-6" X 7'-0"	H. METAL	L-200, SEE SPECIAL SURFACE SCHEDULE	1 3/4"	SOLID	-	-	HW-6
05	HOLLOW METAL	3'-6" X 7'-0"	H. METAL	METAL PAINTED	1 3/4"	HOLLOW	-	-	HW-3
06	-	-	-	-	-	-	-	-	-

HARDWARE SCHEDULE

INSTALLED AND FURNISHED BY..G.C. UNLESS NOTED OTHERWISE

SET	HINGES	CLOSERS	PUSH/PULL	LOCKSET	STOPS	THRES HOLD	ADA SIGNAGE	KICKPLATE	SILENCERS
HW-1 PANIC EXIT REQ	PEMKO FM95HD1	YALE UNI-3501 FIN/COLOR TO MATCH DOOR	ROCKWOOD BF168 TYPE 1 HD MOUNTING FINISH/COLOR TO MATCH DOOR	EXIT DEVICE: ADAMS RITE 8600 C-36-8655 WITH 8650 ESCUTCHEON. YALE CYLINDER (1) K620 X 1160 NOTE: HW-1 CYLINDERS TO BE SMALL FORMAT 7-PIN MORTISE CYLINDER HOUSING WITH SARGEANT CAM.	IVES FS18S FIN/COLOR TO MATCH DOOR	PEMKO 168	-	-	-
HW-1 LOCK-ABLE	PEMKO FM95HD1	YALE UNI-3501 FIN/COLOR TO MATCH DOOR	ROCKWOOD 47-33" (33" CTC) T1HD MOUNTING, FINISH/COLOR TO MATCH DOOR	DEADBOLT: ADAMS RITE MS1851SW X 4016 4085X4089X(2)MS4043 YALE CYLINDER (2) 1194X1160L	IVES FS18S FIN/COLOR TO MATCH DOOR	PEMKO 168	-	-	-
HW-2	NOT USED				-	-	-	-	-
HW-3	PEMKO CFM95HD1	YALE UNI-4410 689 6190	-	LATCH GUARD: McKINNEY LPD1 US32D EXIT DEVICE: YALE 2100-42 689 EXIT ALARM: DETEX EAX-500 WEATHER STRIPPING: PEMKO 303AS, RAIN DRIP: PEMKO 346A	-	PEMKO 168 A	-	IVES 8400 10" X 40" US32D (PUSH SIDE ONLY)	-
HW-4	McKINNEY, MPB79 4.5X4.5 619	YALE 3501-REG 689	-	PRIVACY LOCK YALE AU YMCL 4702LN X 693X497 619	McKINNEY WS02 619	-	McKINNEY-BLACK HCLAV01-M HCLAV01-W	IVES 8400 10" X 34" 619 (BOTH SIDES OF DOOR)	ROCKWOOD 608
HW-5	NOT USED								
HW-6	McKINNEY, MPB79 4.5X4.5 619	-	-	YALE MO 5301LN 619	McKINNEY WS02 619	-	-	IVES 8400 10" X 28" 619 (PULL SIDE ONLY)	ROCKWOOD 608

WALL SCHEDULE

INSTALLED AND FURNISHED BY..G.C. UNLESS NOTED OTHERWISE

NO.	DESCRIPTION
W1	3-5/8" 20GA. METAL STUD WALL W/ 5/8" TYPE "X" GYP. BOARD BOTH SIDES (SEE ARCHITECTURAL DETAILS & ELEVATIONS)
W2	3-5/8" 20GA. METAL STUD WALL W/ 5/8" TYPE "X" GYP. BOARD ON ONE SIDE (SEE ARCHITECTURAL DETAILS & ELEVATIONS)
W3	(2) 3-5/8" 20GA. METAL STUD WALLS W/ 5/8" TYPE "X" GYP. BOARD BOTH SIDES (SEE ARCHITECTURAL DETAILS & ELEVATIONS)
W4	3-5/8" 20GA. METAL STUD LOW WALL W/ 5/8" TYPE "X" GYP. BD BOTH SIDES. PROVIDE 3 1/2" KNEE-WALL BRACE/POST @ CORNERS AND @ 48" O.C.
W5	6" 20GA. METAL STUD WALL W/ 5/8" TYPE "X" GYP. BOARD BOTH SIDES (SEE ARCHITECTURAL DETAILS & ELEVATIONS)
W6	6" 20GA. METAL STUD WALL W/ 5/8" TYPE "X" GYP. BOARD ONE SIDE (SEE ARCHITECTURAL DETAILS & ELEVATIONS)
W7	6" 20GA. METAL STUD LOW WALL W/ 5/8" TYPE "X" GYP. BOARD BOTH SIDES. PROVIDE 3 1/2" KNEE-WALL BRACE/POST @ CORNERS AND @ 48" O.C

WALL PANEL SCHEDULE

INSTALLED AND FURNISHED BY..G.C. UNLESS NOTED OTHERWISE

NO	MANUFACTURER	DESCRIPTION	MFG #	COLOR FINISH	REMARK
WP1	CRANE COMPOSITES INC.	F.R.P. THICKNESS: .075	LBCS.14	#636 (GRAY), SM/SM	CONTACT: LINDA RUSE 310.857.9036
WP2	-	S.S. PANEL (22 GA)	-	BRUSHED FINISH	FURNISHED BY PX, INSTALLED BY G.C.
WP3	-	S.S. PANEL (22 GA)	-	DIAMOND PATTERN FINISH	FURNISHED BY PX, INSTALLED BY G.C.
WP4	NOT USED				
WP6	NOT USED				
W101	NOT USED				
W102	WOLF GORDON	PRINT WALLCOVERING	-	(AT MENU BOARD)	CONTACT: CATHY DY 310.770.1165 cathy.dy@wolfgordon.com

SPECIAL SURFACE SCHEDULE

INSTALLED AND FURNISHED BY..G.C. UNLESS NOTED OTHERWISE

NO	MANUFACTURER	PRODUCT	MFG #	STAIN / COLOR	FINISH	REMARK
QZ-5	SAMSUNG RADIANZ	ARTIFICIAL QUARTZ	TE-215	TETON BEIGE	POLISHED	SERVICE COUNTER & DRINK STATION PROVIDED BY PX, INSTALLED BY G.C.
QZ-6	NOT USED	-	-	-	-	-
QZ-7	SAMSUNG RADIANZ	ARTIFICIAL QUARTZ	-	BLACK GALAXY GRANITE	POLISHED	LAVATORY UNDER MOUNT COUNTER PROVIDED BY PX, INSTALLED BY G.C.
TR-100	SCHLUTER	DILEX-AHK COVE TILE TRIM	AHK 1S 100 ATGB	ANODIZED ALUMINUM	BRUSHED NICKEL	REF. SHEET A-104 FOR MORE INFO
TR-101	SCHLUTER	RONDEC EDGE TILE TRIM	R0100 ATGB	ANODIZED ALUMINUM	BRUSHED NICKEL	REF. SHEET A-104 FOR MORE INFO
L-200	WILSONART	PLASTIC LAMINATE	7949K-18	ASIAN NIGHT	-	INTERIOR RESTROOM DOORS (BOTH SIDES)

INTERIOR PAINT SCHEDULE

INSTALLED AND FURNISHED BY..G.C. UNLESS NOTED OTHERWISE

NO	MANUFACTURER	MFG #	COLOR	FINISH	REMARK
P9As	SHERWIN-WILLIAMS	SW 7065	ARGOS	PROMAR 200, ZERO VOC, LATEX SEMI-GLOSS	REAR SERVICE DOOR
P98	NOT USED				
P101	SHERWIN-WILLIAMS	SW 6252	ICE CUBE	PROMAR 200, ZERO VOC, LATEX EGG-SHELL	RESTROOM & RESTROOM VESTIBULE CEILING
P102	NOT USED				
P103	SHERWIN-WILLIAMS	SW 7032	WARM STONE	PROMAR 200, ZERO VOC, LATEX EGG-SHELL	DROPPED SOFFITS
P104	SHERWIN-WILLIAMS	SW 6155	RICE GRAIN	PROMAR 200, ZERO VOC, LATEX EGG-SHELL	MENU BOARD SOFFIT, DINING RM. WALLS, RESTROOM VESTIBULE WALLS
P105	NOT USED				
P106	SHERWIN-WILLIAMS	SW 7020	BLACK FOX	DTM ACRYLIC GLOSS, LOW VOC	RESTROOM DOOR FRAMES & LCD NICHE (BACK WALL)
P205	SHERWIN-WILLIAMS	SW 7675	SEALSKIN	PROMAR 200, ZERO VOC, LATEX EGG-SHELL	FRONT & BACK & UNDERSIDE FACES OF SERVICE COUNTER SOFFIT

PANDA EXPRESS CHINESE KITCHEN

PANDA RESTAURANT GROUP INC.
1683 Walnut Grove Ave.
Rosemead, California
91770
Telephone: 626.799.9898
Facsimile: 626.372.8288

All ideas, designs, arrangement and plans indicated or represented by this drawing are the property of Panda Express Inc. and were created for use on this specific project. None of these ideas, designs, arrangements or plans may be used by or disclosed to any person, firm, or corporation without the written permission of Panda Express Inc.

REVISIONS:

ISSUE DATE:

1st	ISSUE FOR PERMIT	02-15-17
2nd	ISSUE FOR BID	02-22-17

DRAWN BY: RR

PANDA PROJECT #: S8-17-D4968

ARCH PROJECT #: 1703

RANDY REYNOLDS ARCHITECT
1702 MILDARE COURT □ THOMPSONS STATION, TN 37179
PHONE (615) 591-0675 □ FAX (866) 584-1225

STATE OF GEORGIA — RANDY L. REYNOLDS — 12 — 17 — CERTIFICATE NO. 030788 — REGISTERED ARCHITECT

PANDA EXPRESS
Terraces at Suwanee Gateway (in front of Lowe's)
3276 LAWRENCEVILLE-SUWANEE RD
SUWANEE, GA
2200 TRUE WARM & WELCOME

G-005

SCHEDULES